BRUHAT BANGALORE MAHANAGARA PALIKE

Item No.101

APPROVED SCHEDULE - B

Tender Notification No: BBMP/ EE /Btp/Ten/02/2012-13 Dated: 15-05-2012

Item No. 143

Name of Work: Providing Rainwater Harvesting Structures in ward No.10.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of S NARAYANA SWAMY	
				In Figures	In Words
1	29.91	Earthwork excavation for foundation of buildings,culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5 m and above in width, in hard soil not exceeding 1.5 m in depth including dressing in the bottom and sides of pits and trenches ,stacking the excavated soil clear from edges of excavation with lead upto 50m.after breaking of clods complete as per specificationss and directions of Engineer-In-Charge	Cum	**135.82**	Rupees One Hundred Thirty Five and Eighty Two Paise Only
2	13.26	Earthwork excavation for foundation of buildings,water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5 m in and above in width, in hard soil not exceeding 1.5 m in depth including dressing in the bottom and sides of pits and trenches ,stacking the excavated soil clear from edges of excavation with lead upto 50m.after breaking of clods complete as per specifications and directions of Engineer-In-Charge	Cum	**254.66**	Rupees Two Hundred Fifty Four and Sixty Six Paise Only
	13.26		Cum	**305.60**	Rupees Three Hundred Five and Sixty Paise Only
3	13.26	Excavation 1.5m and above in width in soft rock without blasting for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches not exceeding 1.5m. In depth, stacking the excavated stuff from edges of excavation with lead upto 50m including cost of labours complete as per specifications and directions of Engineer-In-Charge	Cum	**305.60**	Rupees Three Hundred Five and Sixty Paise Only
4	0.33	Providing and laying in position plain cement concrete of mixed 1:4:8 using 40mm and down size graded granite metal machine mixed concrete laid layers not exceeding 15 cms thick, well compacted, in foundation and plinth cost of all materials labour , HOM of machinery , curing complete as per specifications and directions of Engineer-In-Charge	Cum	**4128.50**	Rupees Four Thousand One Hundred Twenty Eight and Fifty Paise Only

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of S NARAYANA SWAMY	
				In Figures	In Words
5	4.46	Providing and constructing burnt brick masonry with approved quality of non-modular bricks of standard size of class designation 50 (table moulded) with cement mortar 1:6 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications.and directions of Engineer-In-Charge	Cum	**5121.75**	Rupees Five Thousand One Hundred Twenty One and Seventy Five Paise Only
6	30.00	KSRB 2900-9.1: Providing and laying reinforced cement concrete pipe NP3 1200mm dia for culverts including pointing ends and fixing collars with cement mortar 1:2 including cost of all labour, curing complete as per specifications. Specification No. KSRB 1000, 2300 MORT & H Specification and directions of Engineer-In-Charge	Rmtr	**9386.35**	Rupees Nine Thousand Three Hundred Eighty Six and Thirty Five Paise Only
7	19.40	Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labours, curing complete as per specifications. and directions of Engineer-In-Charge	Sqm	**150.00**	Rupees One Hundred Fifty Only
8	58.35	Providing and filling in foundation with granite broken metal 100mm and down size with approved sand including and packing ramming,watering including cost of all materials and labour with all lead and lift etc., complete as per specification and directions of Engineer-In-Charge	Cum	**1062.00**	Rupees One Thousand Sixty Two Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92